



## 5478 HW Lot 3 P

### West of Rich's Point

Recommendation is to leave natural





**5174 KS Block 5 P**

**Ascot Beach**

**East reserve parcel**

**Action recommended Restore inland, 3 to 1 slope and revegetate. May need to haul material off site,– Approximate cost \$6,000 - \$8,000**





## Fallis – Beach Way

Action recommended –Reseed south access point; North end reslope 3 to 1, haul material away, potentially need erosion matting; seed wherever access is used, otherwise leave natural Approximate cost \$3,000 - \$5,000







### Fallis south of Beach Way (road allowance)

Action recommended –Where trees/vegetation leave as is; Hand tools or small equipment; re-level, remove excess material. Sediment control; if bigger equipment, winter access will be required. Approximate cost up to \$25,000 (needs to be confirmed)









## Fallis – Railway Avenue

Action recommended –hand tools to level and pull back, re-slope 3 to 1, revegetate. Second property would be more substantial Approximate cost \$7,000









## Plan 1418Ks Block 7 Plot P

Action recommended – cut sod, re-level Approximate cost \$2,000





## Plan 9920182 – 22ER (18 Sundance)

Recommendation is to leave natural





## 6111HW Plan P

Recommendation is to leave natural





## Plan 9522596 Plot 12 ER

Action recommended – remove blocks in winter due to safety (slipping) hazard. Interim measures needed to restrict access other than access to the dock. \$25,000??

